

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22856-01-00
Spot: SESESWSW Sec/Twnshp/Rge: 35-11S-21W
200 feet from S Section Line, 1000 feet from W Section Line
Lease Name: BLISS Well #: 35 #1H
County: TREGO Total Vertical Depth: 8110 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	60		100 sx
PROD	7	4573		650sx
SURF	9.625	318		250 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2017 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE Company: AMERICAN WARRIOR, INC. Phone: (620) 276-2963

Proposed Plugging Method: Ordered 470 sx 60/40 pozmix 4% gel cement, 300 # hulls and 13 sx gel.
DV Tool at 2234' w/350 sx cement.
CIBP at 3500'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3483' and pumped 13 sx gel followed by 50 sx cement. Pulled tubing to 2248' and pumped 350 sx cement. Pulled tubing. Topped off casing with 25 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.04516 -099.62711

Perfs:


INVOICED
JUN 22 2017

Remarks: SWIFT CEMENT TICKET # 30042

Plugged through: TBG

District: 04

Signed



Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 16 2017

CONSERVATION DIVISION
WICHITA, KS

JUN 01 2017