

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-22969-00-00  
Spot: SENENWNE Sec/Twnshp/Rge: 8-8S-21W  
570 feet from N Section Line, 1500 feet from E Section Line  
Lease Name: HART Well #: 1-8  
County: GRAHAM Total Vertical Depth: 3610 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3599		150 SX
SURF	8.625	222		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2017 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOE Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Port Collar set at 1542' w/165 sx cement.  
Perforations: 3352' - 3404'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/25/2017 2:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3393' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 2666' and pumped 80 sx cement. Pulled tubing to 1527' and pumped 115 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 40 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.37813 -099.68228

Perfs:

Top	Bot	Thru	Comments
3478	3481		

INVOICED  
JUN 22 2017

Remarks: SWIFT CEMENT TICKET # 30039

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*(Signature)*  
(TECHNICIAN)

CM

KCC WICHITA  
JUN 02 2017  
RECEIVED