

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23673-00-00
Spot: SWNESESW Sec/Twnshp/Rge: 26-9S-23W
760 feet from S Section Line, 2995 feet from E Section Line
Lease Name: SPARKS Well #: 6
County: GRAHAM Total Vertical Depth: 3975 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3973		150 SX
SURF	8.625	262		165 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/26/2017 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/1000 # hulls and 8 sx gel.
Port Collar at 1982' w/185 sx cement.
Perforations: 3856' - 3860' and 3878' - 3898'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/26/2017 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3825' and pumped 8 sx gel followed by 110 sx cement w/300 # hulls. Pulled tubing to 2049' and pumped 265 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 50 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.23588 -099.85801

Perfs:

Top	Bot	Thru	Comments
3892	3898		
3878	3884		
3856	3860		


INVOICED
JUN 2 2 2017

Remarks: SWIFT CEMENT TICKET # 30040

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA
JUN 02 2017
RECEIVED