

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-01404-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 11-12S-23W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HIXSON C Well #: 2
County: TREGO Total Vertical Depth: 4020 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3990		
L2	3.5	4020		Top 3927'
PROD	5.5	3798		50 SX
SURF	8.625	182		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2017 12:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: BEAR PETROLEUM LLC Company: BEAR PETROLEUM LLC Phone: (316) 524-1225

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 3705' - 3742' and 4005' - 4011'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2017 4:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 2450', 1875', 1050' and 178'. Ran tubing to 3900' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 3205' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2225' and pumped 75 sx cement. Pulled tubing to 1205' and pumped 137 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 5 sx cement. Tied on to backside and squeezed with 2 sx cement.

GPS: 39.02916 -099.84247

Perfs:

Top	Bot	Thru	Comments
3705	3742		

INVOICED
JUN 22 2017

Remarks: COPELAND CEMENT TICKET # 45130

Plugged through: TBG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 16 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUN 13 2017