

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-30400-00-00  
Spot: NESWSESW Sec/Twnshp/Rge: 5-34S-15E  
632 feet from S Section Line, 3580 feet from E Section Line  
Lease Name: TUCKER Well #: 5-1  
County: MONTGOMERY Total Vertical Depth: 1409 feet

Operator License No.: 5817  
Op Name: BENSON MINERAL GROUP, INC.  
Address: 1560 BROADWAY STE 1900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1400		130 SX
SURF	7	7		3 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: KODIAK CONSTRUCTION Company: \_\_\_\_\_ Phone: (620) 505-0479

Proposed Plugging Method: RUN 1 1/2 TUBING TO TD. PUT 5 SACKS OF CEMENT UP TO HALF POINT OF WELL. ADD 5 MORE SACKS. GO UP TO 350 1/2 AND CEMENT SURFACE

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 06/05/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

On 6/2/2017 ran 2" to 1240' gelled hole and spotted 5 sack plug. Pulled up to 500' and spotted 5 sacks plug. Pulled up to 225' and circulated cement to surface. Pulled 2" and topped well off. Came back on 6/5/2017 and ran 2" into 45' and tagged cement. Circulated cement to surface. A total of 36 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
KCC DIST # 3  
JUN 06 2017  
CHANUTE, KS

DS

INVOICED  
JUN 22 2017

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JUN 09 2017  
CONSERVATION DIVISION  
WICHITA, KS

6-9-17