

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-30946-00-00  
Spot: NWSWSESW Sec/Twnshp/Rge: 5-34S-15E  
445 feet from S Section Line, 3635 feet from E Section Line  
Lease Name: TUCKER Well #: 5-3  
County: MONTGOMERY Total Vertical Depth: 1648 feet

Operator License No.: 5817  
Op Name: BENSON MINERAL GROUP, INC.  
Address: 1560 BROADWAY STE 1900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1120		
PKR		1611		PACKER TYPE AND SETTING DEPTH: BAKER @1611'
PROD	5.5	1648		130 SX
SURF	8.625	40		3 SX
T1	2.875	1611		

Well Type: SWD UIC Docket No: D28719.0 Date/Time to Plug:  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: KODIAK CONSTRUCTION Company: Phone: (620) 505-0479

Proposed Plugging Method: RUN 1 1/2 TUBING TO TD. PUT 5 SACKS OF CEMENT UP TO HALF POINT OF WELL. ADD 5 MORE SACKS. GO UP TO 350' AND CEMENT SURFACE

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 06/05/2017 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1610' gelled (mixed with cottonseed hulls) hole and spotted 7 sack plug. Pulled 2" out. Came back on 6/5/2017 and tagged cement at 1575'. Pulled up to 500' and spotted 7 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 2" and topped well off. A total of 42 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
KCC DIST # 3  
JUN 06 2017  
CHANUTE, KS  
DS  
INVOICED  
JUN 29 2017


Remarks:

Plugged through: TBG

District: 03

Received  
KANSAS CORPORATION COMMISSION  
JUN 09 2017  
CONSERVATION DIVISION  
WICHITA, KS

Signed



(TECHNICIAN)

6-9-17