

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-02324-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 14-25S-19E
1342 feet from S Section Line, 5086 feet from E Section Line
Lease Name: SCOTT Well #: K 8
County: ALLEN Total Vertical Depth: 864 feet

Operator License No.: 34784
Op Name: BAYONET PETROLEUM LLC
Address: 1371 3600 ST
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	864		
SURF	8.25	7		

Well Type: EOR UIC Docket No: E14357.31 Date/Time to Plug:
Plug Co. License No.: 33783 Plug Co. Name: MICHAEL DRILLING LLC
Proposal Rcvd. from: RICK MICHAEL Company: MICHAEL DRILLING LLC Phone:

Proposed Plugging Method: Run 1" inside 2" casing to TD. Cement to surface. Run 1" on backside of 2" and cement to surface.

Plugging Proposal Received By: RYAN DULING Witness Type: NONE
Date/Time Plugging Completed: 06/16/2017 11:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing hanging inside the 4.5" casing to 835'. Ran 1" pipe down the backside of the 2" casing inside the 4.5" casing to 210' where cement was encountered. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe out of the 2" casing. Pumped and circulated cement through the 1" pipe on backside of the 2" casing and inside the 4.5" casing from 210' to surface. Pulled the 1" pipe out of the well. Topped the well off with cement. A total of 100 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST #3
JUN 20 2017
CHANUTE, KS

RD

INVOICED
JUN 22 2017

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] RD
(TECHNICIAN)