

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-20549-00-03  
Spot: SESENE Sec/Twnshp/Rge: 33-30S-2W  
2310 feet from N Section Line, 330 feet from E Section Line  
Lease Name: STEWART-ARD Well #: 1  
County: SUMNER Total Vertical Depth: 3807 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>9913</u>	PROD	4.5	3807		50 SX
Op Name: <u>BULLSEYE PETROLEUM, INC.</u>	SURF	8.625	241		200 SX
Address: <u>15820 PLYMOUTH RD</u> <u>WICHITA, KS 67230</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2017 12:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Revd. from: WILLIAM ASH C/O BULLSE Company: BULLSEYE PETROLEUM Phone: (316) 733-5280

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE  
Date/Time Plugging Completed: 05/18/2017 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

RIGGED UP ON WELL 4-13-2017, ENTERED WELL BORE DISCOVERED BRIDGE AT AN APPROX. DEPTH OF 3150' WITH CONTINUOUS RAIN AT LOCATION AND THE NECESSITY FOR ADDITIONAL EQUIPMENT TO PLUG, RIGGED DOWN MOVED OFF LOCATION. RE-RIGGED UP ON WELL 5-18-2017, TALLIED AND RAN 2 3/8" TUBING, WORKED THRU BRIDGE AT THE DEPTH OF 3129-3135' CONTINUING ON TO DEPTH OF 3770'. PUMPED APPROX. 6 BARRELS OF FRESH WATER TO ASSURE TUBING CLEAR OF DEBRIS, MIXED AND SPOTTED 50 SACKS OF COMMON CEMENT, PULLED TUBING. RAIN PERFORATION TOOL, TAGGED CEMENT AT 3317', POSITIONED GUN AT 500-501 FT SHOT WITH 4 HOLES, RIGGED UP EQUIPMENT AND RAN TO 466 FT PUMPED APPROX 12 BARRELS OF FRESH WATER GOT CIRCULATION, MIXED AND DISPLACED CEMENT, CEMENT CIRCULATED TO SURFACE WITH 100 SACKS OF 60-40 COMMON CEMENT, TOPPED OFF CASING. PLUGGING COMPELTE, RIGGED DOWN.

Perfs:

Top	Bot	Thru	Comments
3804	3807		

INVOICED  
JUN 22-2017

Remarks: PLUGGED PER COMPLIANCE AGREEMENT

Plugged through: CSG

District: 02

Signed Jeff Klock, District Supervisor  
(TECHNICIAN)