

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-129-10557-00-01  
Spot: NWNWSENW Sec/Twnshp/Rge: 32-34S-43W  
3873 feet from S Section Line, 3944 feet from E Section Line  
Lease Name: SCOTT A Well #: 1  
County: MORTON Total Vertical Depth: 4180 feet

Operator License No.: 33127  
Op Name: CHAPARRAL ENERGY, L.L.C.  
Address: 701 CEDAR LK BLVD  
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4073		WITH 3 SX CMT
PROD	5.5	4178	0	WITH 800 SX CMT
SURF	8.625	1247		WITH 597 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2017 8:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: JAVIER Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Run tbg, set CIBP @ 4073'. Circulated w/mud & cap 10 sx Class C cmt. EOT @ 2900', mix & spot 40 sx cmt to cover prior squeeze @ 2773'-2888'. Cut & pull free 5-1/2" csg. Run tbg to 1277' & spot 80 sx cmt. EOT @ 350', spot 50 sx cmt. Top out 64'-4' w/20 sx cmt.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/23/2017 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4073' WITH 3 SX CMT. PUMP 40 SX CMT AT 2900' OVER SQUEEZED PERFS 2735' TO 2888'. LOAD HOLE & MAKE BLIND CASING CUT AT 1313'. ATTEMPT TO PULL CASING. WOULD NOT COME AT 110,000#. HAVE 0" STRETCH. APPEARS CASING IS CEMENTED TO SURFACE. RUN TBG TO 1313' & CIRCULATE CMT TO SURFACE WITH 130 SX CMT. TOP OFF WITH 5 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
4123	4133		

INVOICED  
JUN 22 2017

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
SIA (TECHNICIAN)

RECEIVED  
JUN 09 2017  
KCC DODGE CITY