

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22349-00-00
Spot: SESWNWNW Sec/Twnshp/Rge: 10-17S-29W
1315 feet from N Section Line, 520 feet from W Section Line
Lease Name: FOOTE Well #: 1-10
County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 35300
Op Name: COACHMAN ENERGY OPERATING CO
Address: 1125 17TH ST., SUITE 410
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4234		
CIBP		4325		
DVT	5.5	2305		WITH 420 SX CMT
PROD	5.5	4628	0	WITH 180 SX CMT
SURF	8.625	265		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2017 12:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: BOB PLANTE Company: H&C OIL OPERATING Phone: (785) 731-7051

Proposed Plugging Method: PUMP 50 SX CMT, 200# HULLS, GEL SPACER TO 2300' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 05/24/2017 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 50 SX CMT & 200# HULLS, THEN 15 BAGS GEL IN 36 BBL WATER THEN 210 SX CMT & 200# HULLS. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 400#. TIED ONTO BACKSIDE & PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4461	4465		
4239	4243		
4200	4211		
4129	4133		

INVOICED
JUN 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

RECEIVED
JUN 13 2017
KCC DODGE CITY

Signed

Michael Maier
TA

(TECHNICIAN)