

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22284-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 34-16S-29W
1649 feet from S Section Line, 1263 feet from E Section Line
Lease Name: HOLLAMON Well #: 1-34
County: LANE Total Vertical Depth: 4649 feet

Operator License No.: 35300
Op Name: COACHMAN ENERGY OPERATING CO
Address: 1125 17TH ST., SUITE 410
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	2280		WITH 405 SX CMT
PROD	5.5	4649	0	WITH 185 SX CMT
SURF	8.625	216		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2017 12:00 PM
Plug Co. License No.: 8914 Plug Co. Name: H & C OIL OPERATING INC.
Proposal Revd. from: BOB PLANTE Company: H & C OIL OPERATING INC. Phone: (785) 447-7434

Proposed Plugging Method: PUMP 50 SX CMT, 200# HULLS & GEL SPACER TO 2300' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2017 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 50 SX CMT & 200# HULLS THEN 17 BAGS GEL IN 34 BBL WATER THEN 250 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 300#. TIED ONTO BACKSIDE & PUMPED 30 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4547	4559		
4528	4538		
4499	4510		
4465	4495		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed Michael Maier
JA (TECHNICIAN)

RECEIVED
JUN 13 2017
KCC DODGE CITY

Form CP-2/3

INVOICED
JUN 22 2017