

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-099-23781-00-00
 Spot: N2S2SWSE Sec/Twnshp/Rge: 25-31S-17E
640 feet from S Section Line, 1980 feet from E Section Line
 Lease Name: MOBERLY Well #: 15-25
 County: LABETTE Total Vertical Depth: 1028 feet

Operator License No.: <u>5150</u>	String	Size	Depth (ft)	Pulled (ft)	Comment
Op Name: <u>COLT ENERGY INC</u>	CIBP		845		
Address: <u>PO BOX 388</u>	PROD	4.5	1020		110 SX
<u>IOLA, KS 66749</u>	SURF	8.625	22		6 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/12/2017 12:00 AM
 Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
 Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH W/ 2 3/8" TBG TO 844', MIX BENTONITE & WTR THEN PUMP IN SAME ("GEL THE HOLE UP"), THEN PMP IN A 400' CMT PLUG (ENOUGH CMT TO COVER ALL THE PERFS FROM 844 TO 450), PU TBG TO 250', CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL, RETURN AT A LATER DATE, CUT OFF ALL CASING BELOW "BLOW DEPTH", AND CLEAN UP THE LOCATION.

Plugging Proposal Received By: _____ Witness Type: NONE
 Date/Time Plugging Completed: 06/12/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 844' (BRIDGE PLUG AT 845'), "GELLED" THE HOLE UP THEN PMPD IN 440' OF CMT ON BTM, PU TBG TO 256', PMPD IN AND CIRC CMT TO SURF, PULL REST OF TBG, "TOPPED OFF" PROD CSG W/ CMT, PRESS UP TO 350 PSI AND SHUT WELL IN. WILL RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", AND CLEAN UP LOCATION. USED: 2 100 LB SX OF BENTONITE, 1 SX OF COTTON SEED HULLS, AND 65 SX OF PORTLAND CMT (42 SX ON BTM PLUG AND 23 SX ON TOP PLUG)

Perfs:

Top	Bot	Thru	Comments
948	950		
698	700		
621	623		
593	595		
580	582		
554	557		
518	524		
492	700		

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
 (TECHNICIAN)

RECEIVED
 KCC DIST #3
 JUN 22 2017
 CHANUTE, KS
 RH
 INVOICED
 JUN 22 2017