

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-099-23877-00-00  
Spot: SWNESWNE Sec/Twnshp/Rge: 2-31S-17E  
1840 feet from N Section Line, 1910 feet from E Section Line  
Lease Name: ENEGREN Well #: 7-2  
County: LABETTE Total Vertical Depth: 1105 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1097		120 SX
SURF	8.625	21		4 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/12/2017 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1096', MIX UP BENTONITE & WTR, PMP IN SAME THRU TBG ("GEL THE WELL UP"), FOLLOWED BY A 200' CMT PLUG (COVERS PERFS FROM 991' TO 926'), PU TBG TO 770', PMP IN A 220' CMT PLUG (COVERS P'FS FROM 760' TO 568'), PU TBG TO 250', CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG, AND CLEAN UP LOC.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 06/12/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH TBG TO 1095' (2' OFF BTM OF CSG), "GELLED" WELL UP THEN PMPD IN A 200' CMT PLUG ON BTM, PU TBG TO 770', PMPD IN A 220' CMT PLUG, PU TBG TO 253', PMPD IN AND CIRC CMT TO SURF, PULL REST OF TBG, "TOPPED OFF" PROD CSG W/ CMT, PRESS UP TO 300 PSI AND SWI. WILL RETURN AT A LATER DATE TO CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOCATION. USED 2 100 LB SX OF BENTONITE, 1 SX OF COTTON SEED HULLS, 65 SX OF PORTLAND CMT ( 22 SX PLUG ON BTM, 21 SX MID PLUG, 22 SX TOP PLUG)

Perfs:

Top	Bot	Thru	Comments
568	991		

RECEIVED  
KCC DIST # 3  
JUN 22 2017  
CHANUTE, KS

RH

INVOICED  
JUN 22 2017

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine  
(TECHNICIAN)