

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-23626-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 14-32S-17E
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: TREFETHEN Well #: 3
County: LABETTE Total Vertical Depth: 1015 feet

Operator License No.: <u>5150</u>	String	Size	Depth (ft)	Pulled (ft)	Comment
Op Name: <u>COLT ENERGY INC</u>	PROD	4.5	1015		125 SX
Address: <u>PO BOX 388</u> <u>IOLA, KS 66749</u>	SURF	8.625	20		5 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/13/2017 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Revd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1007' (GR-N LOG TD), MIX UP & PMP IN A MIXTURE OF BENTONITE & WTR ("GEL THE HOLE UP"), THEN FOLLOW WITH A 120' CMT PLUG (COVERS PERFS FROM 974' TO 910'), PU TBG TO 780', PMP IN A 50' CMT PLUG (COVERS P'FS FROM 772' UP TO 752), PU TBG TO 640', PMP IN A 130' CMT PLUG (COVERS P'FS FROM 630 UP TO 530), PU TBG TO 250', CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CASING BELOW "PLOW DEPTH", AND CLEAN UP LOC.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 06/13/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 1014', "GELLED" THE WELL UP THEN FOLLOWED IN WITH A 120' CMT PLUG ON BTM, PU TBG TO 780', PMPD IN A 270' CMT PLUG, PU TBG TO 250', PMPD IN AND CIRC CMT TO SURF, PULL REST OF CMT, TOPPED OF PROD CSG W/ CMT, PRESS UP TO 300 PSI AND SWI. WILL RETURN AT A LATER DATE TO CUT OFF ALL CSG BELOW "PLOW DEPTH", AND CLEAN UP LOC. USED: 2 100 LB BAGS OF BENTONITE, 1 SX OF COTTON SEED HULLS AND 71 SX OF PORTLAND CMT (14 SX BTM PLUG, 27 SX MID PLUG, AND 30 SX TOP PLUG)

Perfs:

Top	Bot	Thru	Comments
530	974		

RECEIVED
KCC DIST # 3
JUN 22 2017
CHANUTE, KS
RH
INVOICED
JUN 22 2017

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)