

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30653-00-00
Spot: E2W2NENE Sec/Twnshp/Rge: 27-32S-17E
660 feet from N Section Line, 800 feet from E Section Line
Lease Name: FINK Well #: 27-1
County: MONTGOMERY Total Vertical Depth: 1000 feet

Operator License No.: <u>5150</u>	String	Size	Depth (ft)	Pulled (ft)	Comment
Op Name: <u>COLT ENERGY INC</u>	CIBP		930		
Address: <u>PO BOX 388</u>	PROD	4.5	995		114 SX
<u>IOLA, KS 66749</u>	SURF	8.625	22		6 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/12/2017 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 929', "GEL" THE WELL UP (PMP IN A MIXTURE OF BENTONITE & WTR) FOLLOWED BY A 100' CMT PLUG ON BTM (COVERS P'FS FROM 882-891), PU TBG TO 620', PMP IN A 150' CMT PLUG (COVERS P'FS FROM 599-491), PU TBG TO 250', PMP CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, PRESS UP TO 500 PSI, AND SHUT WELL IN. WILL RETURN AT A LATER DATE TO CUT OFF ALL CASING BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 06/12/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 992', "GELLED" UP WELL THEN PMPD IN A 100' CMT PLUG ON BTM, PU TBG TO 620', PMPD IN A 150' CMT PLUG, PU TBG TO 257', PMPD IN AND CIRC CMT TO SURF, PULL REST OF TBG, "TOPPED OFF" PROD CSG WITH CMT, PRESS UP TO 350+/- PSI AND SHUT WELL IN. WILL RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", AND CLEAN UP THE LOC. USED 2 100 LB SX OF BENTONITE, 1 SX OF COTTON SEED HULLS AND 48 SX OF PORTLAND CMT (14 SX BTM PLUG, 14 SX MID PLUG, AND 20 SX TOP PLUG)

Perfs:

Top	Bot	Thru	Comments
491	891		
RECEIVED KCC DIST # 3 JUN 22 2017 CHANUTE, KS RH			
INVOICED JUN 22 2017			

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)