

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-22710-00-00  
Spot: NESENWNW Sec/Twnshp/Rge: 11-19S-9W  
970 feet from N Section Line, 1070 feet from W Section Line  
Lease Name: LONG LAND Well #: 1  
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3070		
CIBP		3250		
PROD	5.5	3383	1690	175 SX
SURF	8.625	322		200 SX
T1	2.875	3061		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2017 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC. Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/06/2017 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. CIBP'S WERE PREVIOUSLY SET. SAND BOTTOM TO 2800' AND CAP WITH 5 SX'S CEMENT. CUT CASING LOOSE AT 1690', PULL TO 1175' AND PUMP 35 SX'S COMMON WITH 3% CC, PULL CASING TO 775' AND WAIT 1 HOUR. TAGGED CEMENT AT 1000'. PUMPED 35 SX'S COMMON WITH 3% CC AT 775', PULLED CASING ON UP TO 375' AND CIRCUALTED CEMENT TO SURFACE. PULLED CASING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3298	3312	CSG	
3093	3099	CSG	
2928	2932	CSG	

Remarks: COPELAND CEMENT #C-45310.

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED  
JUN 22 2017