

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22702-00-00
Spot: SENENWSW Sec/Twnshp/Rge: 35-18S-9W
2280 feet from S Section Line, 1143 feet from W Section Line
Lease Name: BURDETTE Well #: 1
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3250		
PROD	5.5	3373	1920	175 SX
SURF	8.625	314		200 SX
TI	2.66	3072		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2017 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC. Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 06/08/2017 2:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

CIBP AT 3250' WAS PREVIOUSLY SET. MIRU, SAND BOTTOM TO 2850' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 1920' AND PULL TO 1150'. PUMPED 35 SX'S COMMON WITH 3% CC, PULLED CASING ON UP TO 800'. WAITED 1 HOUR AND TAGGED CEMENT AT 900'. PUMPED 35 SX'S COMMON WITH 3% CC AT 800', PULLED CASING TO 365' AND CIRCULATED CEMENT TO SURFACE. PULLED CASING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3318	3322	CSG	
3278	3284		
2927	2931		

Remarks: COPELAND TICKET #C-45312

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
JUN 22 2017