

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21935-00-00
Spot: NEE2W2NW Sec/Twnshp/Rge: 18-21S-22W
1250 feet from N Section Line, 778 feet from W Section Line
Lease Name: TULL Well #: 1-18
County: HODGEMAN Total Vertical Depth: 4371 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 621 BENTON ST.
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/21/2017 11:45 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Revd. from: MIKE KERN Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 05/21/2017 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

INVOICED
JUN 22 2017

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY HURRICANE.

Plugged through: DP

District: 01

Signed

Kenny Sullivan
SA (TECHNICIAN)

RECEIVED
MAY 22 2017
KCC DODGE CITY