

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-04759-00-00
Spot: S2SWSWNW Sec/Twnshp/Rge: 33-19S-12W
2460 feet from N Section Line, 4950 feet from E Section Line
Lease Name: BUTTON Well #: 1
County: BARTON Total Vertical Depth: 3371 feet

Operator License No.: 3309
Op Name: EAGLE PETROLEUM, INC.
Address: PO BOX 335
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3363		90 SX
SURF	8.625	161		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2017 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RON HICKEL Company: EAGLE PETROLEUM, INC. DBA Phone: (620) 793-2037

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 1500 # gel and 400 # hulls.
Surface pipe has been orange peeled to casing and looks to have cement to surface.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 600' and 175'. Ran tubing to 3350' and pumped 1500 # gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 600'. Circulated cement to surface with 125 sx cement. Pulled tubing. Topped off with 5 sx cement. Tied to backside and it pressured up.

GPS: 38.354729 -098.661369

Perfs:

Top	Bot	Thru	Comments
3363	3379		
3254	3260		
3210	3220		

INVOICED
JUN 29 2017

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

MAY 04 2017

MAY 02 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3