

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-20537-00-00
Spot: SESENE Sec/Twnshp/Rge: 36-33S-11E
2821 feet from S Section Line, 550 feet from E Section Line
Lease Name: RANCH Well #: 168
County: CHAUTAUQUA Total Vertical Depth: 1173 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1173		16 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: _____ Phone: (620) 249-2519

Proposed Plugging Method: Run 1" to 1140 gel hole spot 5 sacks cement pull 1" out perforate at 700' and at 350' ran 1" to 700' spot 10 sacks cement pull up to 350' cement to surface

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 05/16/2017 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report: Ran 1" to 1080' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran back into 700' and spotted 10 sack plug. Pulled 1" out. Hooked onto 4.5" casing and pulled 330' of it out of well. Ran 1" back into 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 100 sacks of cement were used to plug this well.

Perfs: _____
RECEIVED
KCC DIST # 3
JUN 06 2017
CHANUTE, KS
DS
INVOICED
JUN 29 2017

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.
Plugged through: TBG

District: 03 Signed Dale
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
JUN 09 2017
CONSERVATION DIVISION
WICHITA, KS

6-9-17