

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 37-25LOCATION CW 6-SW-SESEC. 13 TWP. 16 RGE. 12-WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 6 Lease A. Hoffman - "A"Operator Natl. Co. of Refinery Corp. Address 820 N. 1st St. Bldg. Wichita - Kans.Field _____ County BartonTotal Depth 3373 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 754 ft. Not Connected
5 1/2" casing set at 3318 ft. - 50 sacks of cement - Plugged
back to 3313 ft with sand & 2 sacks of cement - Shot off
& hulled the 5 1/2" casing - mud to 754 ft. Set rock bridge
& 20 sacks of cement at 670 ft. Shot off & hulled the 10 3/4" casing
mud to 300 ft - rock bridge & 15 sacks of cement at 300 ft -
mud to 30 ft bridge & 15 sacks of cement at the surface.
West Supply Co. - Plugging Contractors

PLUGGING

FILE SEC 13 TWP 16 RGE 12-W
NOOK PAGE 37 LINE 25

C. W. Stough -
District Conservation AgentDate 9-1-52

09-03-52
CONSERVATION
DIVISION
WICHITA, KANSAS