

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

15-009-15761-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1968

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Woodman-Iannitti Drilling Company

Complete Address: 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name Dolechek Well No. 2

Location C SL NW SW Sec. 13 Twp. 16 Rge. 12 (E) (W) X

County Barton Total Depth 3366'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated: Old Cabletool Hole

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 4 P Day 12 Month 8 Year 1968

The Above well was plugged as follows:

Total depth 3366' No surface pipe.

5 1/2 csg set at 3359' cw 30 sc cmt.

Filled 5 1/2 csg with sand (3300-3366') and dumped 5 sx cmt with dump bailer. (3260-3300)

Cutoff and recov. 700' of 5 1/2 csg.

Washed hole down thru tubing to 330' and circ. gel mud to surface.

Set 50 sx cmt plug (180-330) Pulled tubing to 60' and circ. 30 sx cmt to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

DATE 8/14/68  
INV. NO. 8282-11