

15-009-03307-
0000

LEASE NAME DOLECHEK

TYPE OR PRINT

WELL NUMBER #7

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR WOODMAN-IANNITTI OIL COMPANY

SEC. 13 TWP. 16s RGE. 12 (R) or (W)

ADDRESS PO BOX 308; GREAT BEND KS 67530

COUNTY BARTON

PHONE# (316) 792-2921 OPERATORS LICENSE NO. 6588

Date Well Completed 7/20/46

Character of Well OIL

Plugging Commenced 12/30/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/30/93

The plugging proposal was approved on December 27, 1993 (date)

by HERB DEINES (KCC District Agent's Name).

Is ACO-1 filed? N/a if not, is well log attached? Filed W/CP-1

Producing Formation Arbuckle Depth to Top _____ Bottom _____ T.D. 3335'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		350'	0	12-1/2"	350'	NONE
		3335'	0	5-1/2"	3335'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
PERFED 12/30/93 @ 1570' - 800' - 350' (1 ft. 2SPE). Ran 2-1/2" tubing to 2260'. Allied Cementing Co. plugged with 60-40 Poz +10% gel as follows: Spotted 65 sax +150# hulls down tubing. Pressure Zero. Pulled tubing to 1620'. Mixed 110 sax +150# hulls down tubing. Circulated to Surface Pressure 100#. Pulled tubing. Cemented down 5-1/2" w/75/sax. Max. Pressure 300#. SIP 100# Cement circulated to surface between 5-1/2" casing & Surface casing. (OVER)*****

Name of Plugging Contractor Allied Cementing Co. Inc. License No. _____

Address PO Box 31; Russell KS 67665

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WOODMAN-IANNITTI OIL COMPANY JAN 24 1994

STATE OF KANSAS COUNTY OF BARTON, ss.

CONSERVATION DIVISION
Wichita, Kansas

D. J. Iannitti, Partner (~~XXXXXXXXXXXXXXXXXXXX~~) or (Operator) c
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D. J. Iannitti
WOODMAN-IANNITTI OIL COMPANY
(Address) PO BOX 308; GT BEND KS 67530



SUBSCRIBED AND SWORN TO before me this 21st day of January, 19 94

Sharon K. Lingreen
Notary Public

My Commission Expires: May 12, 1996 Sharon K. Lingreen

USE ONLY ONE SIDE OF EACH FORM

(CONTINUED) On Jan 2, 1994, before closing the pit, we checked the cement.
It was 340" below surface, but still in the surface pipe.

On January 4, 1994, we filled to surface w/6.25 yards
of Redi-Mix from Concrete Service, Inc..