

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 24 Twp. 21S Rge. 8 (E) 8 (W)
Location as "NE/CNW/SW" or footage from lines C SW NE

Lease Owner Sterling Drilling Co.
Lease Name Fee Well No. 1
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed February 19 19 70
Application for plugging filed unknown 19
Application for plugging approved unknown 19
Plugging commenced March 29 19 71
Plugging completed April 14, 19 71
Reason for abandonment of well or producing formation unknown
If a producing well is abandoned, date of last production unknown 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Mississippian Depth to top Bottom Total Depth of Well 3393 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3377'	3005'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3350'. Mixed and ran 5 sacks cement thru dump bailer. Squeezed well with 20 sacks mud, 1 sack hulls and 75 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pawnee Drilling Co., Inc.
Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Robert L. Pelster (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Pelster
Robert L. Pelster, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 71

My commission expires April 18, 1972
Theora Holleman Notary Public.

STERLING DRILLING COMPANY
 P. O. Box 129
 Sterling, Kansas 67579

WELL LOG ----- FEE #1

Located: C SW NE, Section 24-21S-8W, Rice County, Kansas

OWNER: Martin Oil and Gas Company and Sterling Drilling Company
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 2, 1970
 COMPLETED: January 8, 1970

TOTAL DEPTH: 3380'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Clay and Sand	Ran 5 joints 8 5/8" 24# casing 156.42' cemented @ 168 K.B.
90 - 175 Red Bed and Shale and Shells	Cemented with 150 sacks 60/40 cement with HA5. Plug down @ 9:20 PM, 1-2-70.
175 - 1526 Shale	
1526 - 2900 Lime and Shale	
2900 - 3005 Lime	
3005 - 3135 Lime and Shale	
3135 - 3290 Lime	
3290 - 3370 Lime and Shale	
3370 - 3380 Miss.	Ran 106 joints 5 1/2" 11# 8rd, tested 4000#, 3387.98' threads off, set @ 3379' with 75 cu. ft. salt saturated Pozmix. K.B. is 10.50' above B.H. Plug down 3:30 AM, 1-8-70.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 30 1971
 CONSERVATION DIVISION
 Wichita, Kansas