

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County. Sec. 24 Twp. 21S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Sterling Drilling Co.

Lease Name Mead Well No. 1

Office Address Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil well

Date well completed June 19 70

Application for plugging filed unknown 19

Application for plugging approved unknown 19


Plugging commenced April 5 19 71

Plugging completed April 14 19 71

Reason for abandonment of well or producing formation no longer economical to produce

If a producing well is abandoned, date of last production unknown 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3394' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3373'	2920'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3330'. Mixed and ran 5 sacks cement thru dump bailer. Squeezed well with 20 sacks mud, 1 sack hulls and 75 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pawnee Drilling Co., Inc.

Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Robert L. Pelster (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Pelster

Robert L. Pelster, Great Bend, Kansas (Address)

Subscribed and Sworn to before me this 19th day of April, 19 71

My commission expires April 18, 1972

Theora Holleman Notary Public

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- MEAD #1  
Located: C NE SW, Section 24-21S-8W, Rice County, Kansas

OWNER: Martin Oil and Gas Company and Sterling Drilling Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 2, 1970  
COMPLETED: June 8, 1970

TOTAL DEPTH: 3370'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 178	Red Bed	Ran 4 joints 8 5/8", 8rd, 20#, RCE 3, new casing. 161' pipe set @ 173 K.B. Cemented with 160 sacks HA5, Plug down 12:30 AM, 6-3-70.
178 - 1340	Shale	
1340 - 3025	Lime and Shale	
3025 - 3240	Lime	
3240 - 3370	Lime and Shale	Ran 109 joints 5 1/2" 14# 8rd tested 4000#, 3383.47', threads off, set @ 3369' with 75 cu. ft. salt saturated cement. Plug down 6-8-70 @ 3:30 AM.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 30 1971  
CONSERVATION DIVISION  
Wichita, Kansas