


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 24 Twp. 21 Rge. 8 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NE
Lease Owner Sterling Drilling Company
Lease Name Wilkey #1 Well No.
Office Address Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10/6/71 19
Plugging completed 10/12/71 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation Depth to top Bottom Total Depth of Well 3399 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	171	none
				5 1/2"	3402'	2901'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, ran sand to 3360', dumped 5 sacks of cement. Loaded hole, shot pipe at 2911', spotted 65 barrels oil behind casing. Worked pipe loose and pulled 88 joints. Bailed fluid to 210', set rock bridge to 200' and dumped 25 sacks of cement. Mud to 40' rock bridge and ran 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1971
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet)
Address KNIGHT CASING PULLING CO., INC.
CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and Sworn to before me this 14th day of October, 1971

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1971
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG ----- WILKEY #1

Located: SE NE, Sec. 24-21S-8W, Rice County, Kansas

OWNER: Martin Oil and Gas Company and Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 20, 1969

COMPLETED: December 31, 1969

TOTAL DEPTH: 3403'

<u>LOG</u>		<u>CASING RECORD</u>
0 -	50 Sand and Gravel	Ran 4 joints 8 5/8" casing (159.76')
50 -	176 Clay and Shale	Set @ 171' K.B. with 160 sacks Pozmix with HA-5. Plug down @ 3:30 PM, 12-20-69, by Howco.
176 -	1040 Shale	
1040 -	2995 Shale and Lime	
2995 -	3087 Lime	
3087 -	3190 Lime and Shale	
3190 -	3350 Lime	
3350 -	3403 Lime and Shale	Ran 104 joints 5 1/2" 11# 8RD tested 4000#, 3403.97' threads off, set @ 3402' with 75 cu. ft. salt saturated cement. Shoe at 28.63'. K.B. is 10.50' above B.H. Plug down 8:15 PM, 12-31-69.