

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 18 Twp. 21^S Rge. 8^W (XX)(W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Wilkinson Drilling, Inc.

Lease Name Smisor Well No. #1

Office Address 805 Union Center, Wichita 2, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 6/12/ 1961

Application for plugging filed 6/12/ 1961

Application for plugging approved 6/12/ 1961

Plugging commenced 6/12/ 1961

Plugging completed 6/12/ 1961

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 3572' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @240' w/ 1/2 sacks Hulls & 20 sacks Cement, Top plug @35' w/ 1/2 sack Hulls & 10 sacks Cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wilkinson Drilling, Inc. #363
Address 805 Union Center, Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Walter M. Wilkinson (employee of owner) of (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 1961

Carolyn Iverson
Carolyn Iverson Notary Public.

My commission expires January 2, 1965

WILKINSON DRILLING, INC.

805 UNION CENTER
WICHITA 2, KANSAS

June 14, 1961

DRILLERS LOGWilkinson Drilling, Inc.
SMISOR No. 1NW NW SE, Sec. 18-21S-8W
Rice County, Kansas

Contractor:	Company Tools
Commenced:	June 1, 1961
Completed:	June 11, 1961
Elevation:	1658 Kelly Bushing
Surface Casing:	8 5/8" @ 265' we/175 sacks cement
Total Depth:	3572'

FIGURES INDICATE BOTTOMS OF FORMATIONS:

<u>Depth</u>	<u>Formation</u>
0 - 208	Clay and sand
208 - 230	Anhydrite
230 - 393	Red bed
393 - 1390	Shale and shells
1390 - 1572	Shale
1572 - 2173	Shale and lime
2173 - 2695	Lime and shale
2695 - 2780	Lime
2780 - 2870	Shale
2870 - 3230	Lime and shale
3230 - 3250	Chert
3250 - 3300	Lime
3300 - 3350	Shale
3350 - 3390	Sand and shale
3390 - 3440	Lime and dolomite
3440 - 3470	Dolomite
3470 - 3498	Sand and shale
3498 - 3572	Arbuckle dolomite

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1961

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the log on the Smisor No. 1, located in the NW NW SE of Section 18-21S-8W, Rice County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson

Walter M. Wilkinson-Pres.

Subscribed to before me and sworn to before me this 14th day of June, 1961.

My commission expires Jan. 2, 1965.

Carolyn K. Iverson
Carolyn K. Iverson-Notary Public