

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 34 Twp. 21 S Rge. (E) 8 (W)

Location as "NE/CNW%SW%" or footage from lines Center NE-SE

Lease Owner The Pure Oil Company

Lease Name Floyd Miller Well No. 1

Office Address PO Box 9545 - Oklahoma City 18, Oklahoma.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 25th 19 61

Application for plugging filed August 28th 19 61

Application for plugging approved Verbally approved Aug. 26th 19 61


Plugging commenced August 26th 19 61

Plugging completed August 26th 19 61

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Cecil M. Jones

Producing formation None Depth to top - Bottom - Total Depth of Well 3416 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
None				8-5/8"	262'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with rotary mud to 255' from surface. Dumped 1/2 sack cottonseed hulls @ 255' then dumped 20 sacks cement on hulls, filling 8-5/8" casing to 192'. Filled with rotary mud to 40' from surface. Dumped 1/2 sack cottonseed hulls at 40', then filled 8-5/8" casing to surface with 10 sacks cement. Screwed steel cap on 8-5/8" casing.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert & Jones Drilling Company

Address 514 Orpheum Bldg., Wichita 2, Kansas.

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
I. J. J. Wasicek

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. J. J. Wasicek  
Box 9545 - Oklahoma City, Oklahoma.  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of September, 19 61

My commission expires 4/14/64

John A. Stallard  
Notary Public.

GABBERT-JONES DRILLING CO., INC.  
WICHITA, KANSAS  
DRILLERS WELL LOG

FLOYD MILLER #1  
C NE SE SECTION 34-21S-8W  
RICE COUNTY, KANSAS

COMMENCED: AUGUST 18, 1961  
COMPLETED: AUGUST 26, 1961

OPERATOR - THE PURE OIL COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	137	SURFACE CLAY	
137	267	SHALE	RAN 267' OF 8-5/8" CASING, SET @ 262' W/ 300 SACKS CEMENT.
267	425	RED BED	
425	1095	SHALE	
1095	1480	LIME & SHALE	
1480	1520	LIME	
1520	1735	LIME & SHALE	
1735	2120	LIME	
2120	2790	LIME & SHALE	
2790	3325	LIME	
3325	3390	LIME & CHERT	
3390	3416	LIME	
3416	TD		DRY & ABANDONED

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLERS WELL LOG FOR THE WELL DRILLED IN C NE SE SECTION 34-21S-8W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*E. E. Hall*  
E. E. HALL

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 28TH DAY OF AUGUST, 1961, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1963

*Vira A. McKenzie*  
VIRA A. MCKENZIE, NOTARY PUBLIC