

RECEIVED
STATE CORPORATION COMMISSION
OCT 07 1982
CONSERVATION DIVISION
Wichita, Kansas

15.009.30914.00.01

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- OWWO

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Midway Drilling, Inc.

Complete Address P.O. Box 1325, Great Bend, Ks. 67530

Lease Name Turgeon Well No. 1

Location SE SW NW Sec. 9 Twp. 16 Rge. 12 (East) (West) (West)

County Barton Total Depth 3333'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. _____

Operation Completed: Hour: 10:30 AM Day: 30 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 236' S.P. cas. w/ cement, 4 1/2" set at 3330' w/ 100 sacks cement.

Plugged back 1400' w/ sand & 4 sacks cement, shot pipe 3 times & recovered 818'.

Ordered 140 sacks 50% permix - 4% Sol., - 3% G.L. Cl., 5 sacks bull, 10 sacks Sol. 4 5/8" plug.

Pumped in 8 5/8", 4 sacks bull, 10 sacks Sol., 70 sacks cement, release plug w/ 1 sack bull.

& followed w/ 70 sacks cement

Amount of Surface Casing: 236' of 8 5/8" Medium pressure 750 pounds

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 10-14-82

INV. NO. 1342-U

Signed: _____
Conservation Division Agent