


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Hodgeman County. Sec. 3 Twp. 21 Rge. 23 (EX) (W)
Location as "NE/CNW/SW" or footage from lines C SW/4 NE/4
Lease Owner Edward J. Ackman
Lease Name Frusher Well No. 7-3
Office Address 1600 Broadway Suite 1940, Denver, CO 80202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-21-80 19
Application for plugging filed 10-21-80 19
Application for plugging approved 10-21-80 19
Plugging commenced 10-21-80 19
Plugging completed 10-21-80 19
Reason for abandonment of well or producing formation Objective, Tight

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation None Depth to top Bottom Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	429	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well was full with 9.9 Lb/Gal mud at time of plugging.

- 60 sx at 900'
- 35 sx at 660'
- 10 sx at Surface
- 5 sx at Rat Hole

STATE CORPORATION COMMISSION

NOV 10 1980

11-10-1980

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Colorado, COUNTY OF Denver, ss.
Ric Morgan (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ric Morgan
1600 Broadway Suite 1940, Denver, CO 80202
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of November, 19 80

My commission expires August 18, 1984
Joan M. Carlson
Notary Public.

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

IMPORTANT
Kans. Geol. Survey request
samples on this well.


S. 3 T. 21 R. 23 W

Loc. C SW NE

API No. 15 — 083 — 20,758.6000
County Number

County Hodgeman

640 Acres
N



Elev.: Gr. 2275

DF _____ KB 2289

Operator Edward J. Ackman, dba Advantage Resources, Inc.

Address 1600 Broadway Suite 1940, Denver, CO 80202

Well No. 7-3 Lease Name Frusher

Footage Location 1980 feet from (N) line 1980 feet from (E) line

Principal Contractor Simmons Drilling Co. Geologist J. Jespersen

Spud Date 10-11-80 Date Completed 10-21-80 Total Depth 4550 P.B.T.D. N/A

Directional Deviation 1/2° Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28#	429	Common	225	2% Gel 3% KCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
CONSERVATION DIVISION Wichita, Kansas	

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Operator Edward J. Ackman dba Advantage Resources, Inc.

Well No.

7-3

Lease Name

Frusher

Dry Hole

S 3 T 21 R 23 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Mississippian	4456		Anhydrite	1489
			Base Anhydrite	1502
			Heebner	3780
			Toronto	3793
DST No. 1 4448-85 Misrun			Lansing	3830
			Base KC	4167
DST No. 2 4398-85			Marmaton	4174
15-60-30-30			Pawnee	4290
Rec. 15' mud w/NSO			Ft. Scott	4360
FP 22-22, 34-34			Cherokee Sh	4390
SIP 458-160			B. Ch. Lime	4424
NP 2436-2425			Miss	4456

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Ric Mays
Signature

Exploration Manager

Title

11-6-80

Date