

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Hodgeman County. Sec. 27 Twp. 21S Rge. 21WE/4W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
440' FNL & 660' FWL

Lease Owner Harrell & Bradshaw, Inc.  
Lease Name Leadley Well No. 1

Office Address Suite 1830, One Williams Ctr., Tulsa, OK  
Character of Well (Completed as Oil, Gas or Dry Hole) 74172  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed July 27, 1979  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced July 27, 1979  
Plugging completed July 27, 1979  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,316'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	422'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,316' (rotary total depth) to  
680 ft. Set plug at 680 ft. and cemented with 60 sacks cement. Filled  
hole with heavy rotary mud from 680 ft. to 400 ft. Set plug at 400 ft.  
and cemented with 30 sacks cement. Filled hole with heavy rotary mud  
from 400 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar  
with 10 sacks cement, 3 sacks cement in rat hole.


Plugging operations accomplished utilizing Halliburton Services Oil Well  
cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Services Aug 6 1979  
410 Union Center Bldg., Wichita, Kansas 67202 8-6-79  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent ~~XXXXXXXXXXXXXXXXXXXX~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)



SUBSCRIBED AND SWORN TO before me this 3rd day of August, 1979

My commission expires July 25, 1982  
Elsie Willison - Notary Public.

KANSAS DRILLERS LOG

COMPANY Harrell & Bradshaw, Inc.

SEC. 27 T. 21S R. 21W  
LOC. 440' FNL & 660' FWL

FARM Leadley NO. 1

COUNTY Hodgeman

ROTARY TOTAL DEPTH 4,316'  
COMM. July 18, 1979 COMP. July 27, 1979  
CONTRACTOR H-30, Inc. (Rig #2)  
ISSUED August 3, 1979

CASING

10 3/4"  
8 5/8" Set at 422' cemented w/250 sxs cement  
5 1/2"  
4 1/2"

ELEVATION 2,132' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	1,130'
Sand and Red Bed	1,263'
Anhydrite	1,291'
Shale	1,747'
Shale and Lime	2,045'
Lime and Shale	2,190'
Shale	2,572'
Lime and Shale	2,772'
Shale	2,910'
Lime and Shale	3,727'
Lime	3,840'
Lime and Shale	3,920'
Lime	4,316'
Rotary Total Depth	4,316'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
Dean Britting

State of Kansas }  
County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 3rd day of August, 1979.



*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires: July 25, 1982

RECEIVED  
STATE CORPORATION COMMISSION

AUG - 6 1979

WICHITA DIVISION  
Wichita, Kansas