


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 22 Twp. 21S Rge. 21W (W)
Location as "NE/CNW/SW" or footage from lines 1980' F/NL & 1830' F/WL
Lease Owner Phillips Petroleum Company
Lease Name WATERHOUSE-AB Well No. 2
Office Address Box 287 - Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dry Hole - P&A 11-10-73
Application for plugging filed Verbal approval received 11-10-73
Application for plugging approved 19
Plugging commenced 11-10-73 19
Plugging completed 11-10-73 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Verbal approval 11-10-73

Name of Conservation Agent who supervised plugging of this well Mr. E.J. Eves - Sublette, Kansas
Producing formation Miss Depth to top 4317 Bottom 4350 Total Depth of Well 4350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Water	4317	4350	8-5/8" OD	1261'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran DP open end, circ, spotted cmt plug 4320-4220' w/50 sx reg, spotted cmt plug 1330-1230' w/40 sx reg, spotted cmt plug 900-800' w/35 sx reg, bridged at 45' & cmtd to surf w/15 sx reg. Filled w/mud between plugs. Hallib completed cmt job @ 6:20 AM, 11-10-73.

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slawson Drilling Company
Address One-Twenty Building - Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
C. D. Dohrer (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Prod. Supt.
Box 287 - Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1973

My commission expires 10-27-77 Notary Public.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDOW, ETC.:

15.083.20326.0000

Operator
 PETROLEUM CO.

Well No. Lease Name
 WATERHOUSE AB

Dry Hole

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale & SHELLS	0	575	Anhydrite	1263
REDBED	575	615		
SAND	615	630	Heebner	3636
SAND SHALE	630	1200	Toronto	3656
SHALE SHELLS	1200	1263	Lansing	2702
ANHYDRITE	1263	1278	B.K.C.	4263
SHALE - RED BED	1278	1635	Mississippi	4317
SHALE & SHELLS	1635	2150		
LIME & SHALE	2150	2509		
LIME	2509	2875		
LIME w/ SHALE STREAKS	2875	3702		
L.K.C.	3702	4263		
LIME	4263	4317	Ran GR Guard	
MISSISSIPPI	4317		Density log	4350
LIME		4350		

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 15 1978
 CONSERVATION DIVISION
 Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>C. S. Dohrer</i>
	Signature
	Title
	Date