


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Barton County. Sec. 26 Twp. 16 Rge. (E) 12(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NW NE
Lease Owner Harms and Knight Drilling Co.
Lease Name Dolechek Well No. 1
Office Address Box 184, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-24 1951
Application for plugging filed 3-24 1951
Application for plugging approved 3-24 1951
Plugging commenced 3-24 1951
Plugging completed 3-24 1951
Reason for abandonment of well or producing formation.....
If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3413 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|-----|-------|---------|------------|
| | | 0 | 222 | 8 5/8 | 3-16-51 | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Set bottom plug @ 222' - cemented w/ 15 sks, cement.
Set top plug @ 30' - Cemented w/ 10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1951
4-13-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harms and Knight Drilling Co.
Address Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. W. Railsback (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Railsback
1902 Broadway, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of March, 1951

Betty R. Rader
Notary Public.

My commission expires Aug 4, 1954

23-7877-8 4-49-10M
PLUGGING
FILE SEC 26 T 16 R 12 W
BOOK PAGE 26 LINE 1

WELL LOG

Harms And Knight Drilling Company
Dolechek # 1

Section 26 - T16 - R 12W
NE/4 NW/4 NE/4
Barton County

Total Depth 3413'
Comm: 3-14-51. Comp: 3-24-51
Contractor: Harms & Knight Drilling Co.
Rotary: 0-3413'

Production: Dry

Casing Record: 8 5/8" set at 222' - Cemented w/150 sacks cement - circulated

Figures indicate bottom of formations:

| | |
|----------------------|------|
| Cellar | 5 |
| Clay | 40 |
| Shale & Shells | 100 |
| Sand | 115 |
| Shale | 185 |
| Sand | 197 |
| Shale | 222 |
| Shale & Shells | 424 |
| Sand | 524 |
| Shale & Shells | 580 |
| Red Bed & Blue Shale | 775 |
| Shale & Shells | 793 |
| Anhydrite | 818 |
| Shale | 1000 |
| Shale & Shells | 1450 |
| Lime & Shale | 1780 |
| Shale & Shells | 1845 |
| Sand | 1872 |
| Lime & Shale | 2160 |
| Shale & Shells | 2255 |
| Shale | 2475 |
| Shale & Lime | 2750 |
| Lime | 2990 |
| Lime & Shale | 3090 |
| Lime | 3202 |
| Lime & Shale | 3264 |
| Lime | 3324 |
| Lime & Shale | 3410 |
| Conglomerate | 3413 |
| Total Depth | 3413 |

RECEIVED
APR 13 1951
MISSOURI

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

HARMS & KNIGHT DRILLING COMPANY

By *J. W. Haisbach*
Subscribed and sworn to before me this 1st day of April, 1951

Betty R. Rader
Notary Public

My Commission expires:
Aug 4 1954

PLUGGING
FILE SEC 26 T 16 R 12W
BOOK PAGE 70 LINE 1