

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-009-06628-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barton County, Sec. 26 Twp. 16S Rge. 12 (E) W(W)  
Location as "NE/CNW&SWK" or footage from lines SW SW SE  
Lease Owner The Vickers Petroleum Co., Inc.  
Lease Name Harzman Well No. 1  
Office Address Box 2240, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 29 19 52  
Application for plugging filed July 29 19 52  
Application for plugging approved July 29 19 52  
Plugging commenced July 30 19 52  
Plugging completed July 30 19 52  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough, Great Bend, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3436 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	317	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Set plug @ 300' dump 30 sx cement. Filled w/ mud to 30'  
Set plug @ 30' dumped 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 5 1952

8-5-52

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Jayhawk Drilling Co., Inc.  
Address Box 2240, Wichita, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
John M. Little (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little  
Box 2240, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 31 day of July, 19 52

Allen P. Denton  
Notary Public.

My commission expires August 13, 1953

24-2675-5 2-52-20M

PLUGGING  
FILE SEC 26T-16R-124  
BOOK PAGE 34 LINE 26

THE VICKERS PETROLEUM CO., INC.

Harzman Well #1  
 SW SW SE, Sec. 26-16S-12W  
 Barton County, Kansas

Casing Record  
 8 5/8" @ 317' w/ 165 sx

Commenced: July 17, 1952  
 Completed: July 29, 1952

Elevation: 1936 R.B.  
 D & A

LOG

Surface & Rock	0- 50	Drill Stem Test 3135-3156, open 45 min. weak
Shale & Sand	50- 320	blow 25 min. and died. Recovered 10' mud slight
Sand, Shale & Sand Rock	320- 385	odor, trace oil. No B.H.P. Recorded because
Sand	385- 475	packer failure when tool closed.
Sand Rock, Pyrite	475- 490	
Shale & Sand	490- 570	Drill Stem Test 3410-3424 open 1 Hr. Recovered
Red Beds, Shale, Red Rock, Pyrite	570- 800	18' mud, no show, weak blow 40 min. B.M.P. 195#
Anhydrite	800- 830	
Red Beds, Shale & Shells	830-1050	Drill Stem Test 3422-3436 open 1/2 hr. strong blow
Shale & Shells	1050-1200	throughout test. Recovered 630' salt water S.S.O.
Salt, Shale & Shells	1200-1440	I.F.P. 30# F.F.P. 270# B.M.P. 1010#
Shale & Lime	1440-1575	
Lime & Shale	1575-1740	
Lime Broken, Sand	1740-1820	
Lime Broken, Shale	1820-1945	
Lime Broken	1945-2025	
Shale & Lime	2025-2230	
Lime & Shale	2230-2360	
Shale & Lime	2360-2610	
Lime & Shale	2610-2830	
Lime	2830-3012	
Lime & Shale	3012-3050	
Shale & Sand	3050-3116	
Shale & Lime	3116-3135	
Lime & Little Shale	3135-3364	
Shale	3364-3391	
Conglomerate Chert	3391-3408	
Dolomite	3408-3436	T.D.

SAMPLE TOPS

Heebner	3020
Toronto	3035
Douglas	3050
Brown Lime	3116
Lansing	3135 (1199)
Base Kans. City	3364
Cherty Conglomerate	3391
Arbuckle	3408

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 AUG - 5 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

BY James T. Walker

Subscribed and sworn to before me this 4th day of August 1952.

Allen J. Denton  
 NOTARY PUBLIC

My Commission expires August 13, 1953.

**PLUGGING**  
 FILE SEC 26 T. 16 R. 12W  
 BOOK PAGE 34 LINE 26