

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Barton County. Sec. 26 Twp. 16 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Trans Era Petroleum, Inc.
Lease Name Dolecheck Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6/30/52 19
Application for plugging filed 10/17/53 19
Application for plugging approved 10/17/53 19
Plugging commenced 10/18/53 19
Plugging completed 10/24/53 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3377' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	307	None
				5 1/2"	3376	2310

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Plugged back with crushed rock from 3393' to 3350', dumped 5 sax cement with dump bailer at 3350', top of cement 3315'. Filled hole with mud to 300', set rock bridge, dumped 20 sax cement. Top of cement 240'. Filled with mud to 35', set rock bridge dumped 10 sax cement for cap.

RECEIVED
STATE OF KANSAS
NOV 5 1953

11-5-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Russell, Kansas
(Address)


SUBSCRIBED AND SWORN to before me this 4th day of November, 19 53.

Margie Cooper

Notary Public.

My commission expires 1-30-57

24-7388-5 3-53-20M



B & R Drilling, Inc.
Barton County, Kansas

SE SE SW of Sec. 26-16-12
Dolecheck #1

Total Depth: 3377'
Comm. 6/11/52
Comp. 6/30/52

Casing

8 5/8" Set @ 307'
5 1/2" Set @ 3376'

Cement

165 sacks of Portland
50 sacks of Lehigh

Formation	Depth
Surface soil-clay	15
Post rock	40
Shale-lime-shells	70
Lime-sand	100
Shale-sand-shells	155
Shale-shells	260
Sand	380
Shale-shells	300
Shale	395
Sand	480
Sand-shale	535
Red bed	590
Shale-red bed	790
Anhydrite	870
Lime-shale-shells	970
Shale-shells	1200
Shale-salt	1380
Shale-shells	1660
Shale-lime	3115
Lime	3138
Lime-shale	3149
Lime	3255
Lime-shale	3340
Cherty lime-shale	3350
Lime-shale	3366
Conglomerate	3372
Conglomerate	3375
Arbuckle	3377'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and
correct to the best of my knowledge.

Car. Bety

STATE CORPORATION COMMISSION

OCT 15 1953

Subscribed and sworn to before me this 2nd day of July, 1952.

CONSERVATION DIVISION
Wichita, Kansas

Margie Cooper

Notary Public

My commission expires: 1-30-57
~~6-17-57~~

PLUGGING
FILE SEC 26-16-12-4
BOOK PAGE 135 LINE 41