


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-009-07193-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 26 Twp. 16 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW/ NW/ NW/
Lease Owner Morgenstern & Specter
Lease Name Dolechek "B" Well No. 2
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 2-23-50 19
Application for plugging filed September 21, 1960 19
Application for plugging approved September 22, 1960 19
Plugging commenced 10/2/60 19
Plugging completed 10/6/60 19
Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Trian, Russell, Kansas
Producing formation Arbuckle Depth to top 3373 Bottom 3376 Total Depth of Well 3388 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	316 ft.	none
				5 1/2" OD	3373 1/2'	286 1/2 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 3360 feet. Dumped 5 sacks Cement.
Circulated Mud at 400 feet. Pumped 25 sacks Cement at 250 feet.
Mudded to 40 feet. Set a Rock Bridge at 40 feet.
Dumped 10 sacks Cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1960

CONSERVATION DIVISION
Wichita, Kansas

10-28-1960

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor LYNCH CASING PULLING COMPANY NO. 457
Address R. Rt. 4 GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Specter, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

SUBSCRIBED AND SWORN to before me this 11th day of October, 1960

My commission expires May 7, 1964
[Handwritten Signature] Notary Public.




WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
500 East Murdock Wichita, Kansas

Company THE VICKERS PETROLEUM CO., INC.
Form Dolphak "B" 2

SEC. 26 T. 16 R. 12W
NW NW NW

Total Depth 3388
Comm. 2-1-50 Core 23-50
Shot or Treped.
Contractor.
Issued. 4-0-50

County. Barton
KANSAS



CASING:
8 5/8" @ 316' w/165 sx
5 1/2" @ 3373 1/2' w/75 sx

Elevation. _____

Production. Pot. 316 BOPD - 2%
water

Figures Indicate Bottom of Penetrations.

shale & shalls	188
shale shalls & sand	316
sand shale & shalls	555
rodbod & shale	810
anhydrite	835
shale & shalls	1265
shale shalls & salt	1440
shale & limo	1450
limo broken	1600
limo & sand	1915
limo	1965
limo broken	2085
limo & shale	2710
limo	3033
shale & sand	3096
limo & shale	3373
dolomite	3376
Rotary Total depth	3376
limo	3388
Total Depth-Cable	3388

Tops:

Heebnor	3004
Brown Lansing	3096
White Lansing	3115
Arbucklo	3373

Remarks:

D.D. 3376-3378. Swabbed 5.71 bbls. oil after setting 15 hrs. no water. Acidized w/500 gals. 350' oil in hole 15 hrs. 100' water. DD 3378-3388, 1100' oil in hole 14 hrs. Acidized w/500 gal. 1750' fluid in hole 14 hrs. No water. Swabbed 6.68 B.F. P. H.