


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plot

Barton County, Sec. 26 Twp. 16S Rge. 12 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NW NW
Lease Owner The Vickers Petroleum Co., Inc.
Lease Name Dolechek "B" Well No. 1
Office Address 201 W-K-H Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 1-27-49, Drilled Deeper Feb. 27, 19 50
Application for plugging filed April 17 19 50
Application for plugging approved April 17 19 50
Plugging commenced April 17 19 50
Plugging completed April 21 19 50
Reason for abandonment of well or producing formation Oil depleted

If a producing well is abandoned, date of last production March 28 19 50
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough, Great Bend, Kansas
Producing formation Basal Sand Depth to top 3367 Bottom 3373 Total Depth of Well 3381 Feet
Show depth and thickness of all water, oil and gas formations. Drilled Deeper to 3412 $\frac{1}{2}$

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	310'	
				5-1/2"	3365'	2817'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with rock 3412 to 3350'. Dump 5 sx cement @ 3350'. Filled hole w/mud to 310'. Set rock bridge. Dump 15 sx cement, top of cement 260'. Filled w/mud to 35'. Dump 10 sx cement for cap.

RECEIVED
Conservation DIV.
MAY 29 - 1950
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to The Vickers Petroleum Co., Inc.
Address 201 W-K-H Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John M. Little (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little
201 W-K-H Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of May, 19 50.
Allen P. Denton, Notary Public.

My commission expires August 13, 1953

PLUGGING
FILE SEC 16T 16 R 12W
BOOK PAGE 2 LINE 20

THE VICKERS PETROLEUM CO., INC.

Dolechek "B" Well #1
NE NW NW Sec. 26-16S-12W
Barton County, Kansas

Casing Record:
8-5/8" @ 310' w/155 sx.
5-1/2 @ 3365' w/60 sx.

Commenced: December 27, 1948
Completed: January 27, 1949

Elevation: 1926 R.B.
Poten. Est. 10 B.O.P.D.

L O G

Surface, Clay & Sand	0-130
Shale & Shells	130-310
Shale & Sand	310-540
Shale & Red Bed	540-635
Red Bed & Shale	635-807
Anhydrite	807-835
Shale & Shells	835-1225
Shale & Salt	1225-1485
Lime Broken	1485-2040
Lime & Shale	2040-2665
Lime	2665-2996
Lime & Shale	2996-3031
Sand & Shale	3031-3091
Lime & Shale	3091-3112
Lime, Shale Streaks	3112-3361
Shale	3361-3365
Sand	3365-3371 R.T.D.
S.L.M.	3371-3373

Cable Tools:
Drilled Deeper 6"
Drilled Deeper 1'

Fill up 200' oil - no water - 16 hrs.
White Sand - No Porosity
Fill up 225' oil 16 hrs.

Shot w/5 qts.
Drilled Deeper 6 1/2'

No help.
Sand White Micaceous, tight, No increase
in fluid ← 3381 T.D.

Shot up 20 qts. no increase

Tops:
Brown Lansing
White Lansing
Basal Sand

3091'
3112'
3367' (corr)

3091
RECORDED
INDEXED
FEB 1 1950

I hereby certify that this log is true and correct to the best of my knowledge and belief.


THE VICKERS PETROLEUM CO., INC.

By H. C. Davis

Subscribed and sworn to before me this 8 day of February, 1949.

Allen J. Denton
Notary Public

My commission expires August 13, 1949.



(See attached)

THE VICKERS PETROLEUM CO., INC.

Dolechek "B" well #1
NE NW NW Sec. 26-16S-12W
Barton County, Kansas

Casing Record:
8-5/8" @ 310' w/155 sx
5-1/2" @ 3365' w/60 sx

Commenced: December 27, 1948
Completed: January 27, 1949.

Elevation: 1926 R.B.
Poten. Est. 10 B.O.P.D.

L O G

O. W. D. D. February 27, 1950
O. T. D.

3381

Drilled Deeper

3381-3412 $\frac{1}{2}$

Micaceous Quartzitic Sand
Quartzite

3381-3410
3410-3412 $\frac{1}{2}$ T.D.

D & A

I hereby certify that this log is true and correct to the best of my knowledge and belief.

The Vickers Petroleum Co., Inc.

By

H. C. Davio

Subscribed and sworn to before me
this 25th day of April, 1950.

Allen P. Dinton
Notary Public

My commission expires August 13, 1949.

RECEIVED
REGISTRATION DIV.
MAY 9 - 1950
STATE CORPORATION
COMMISSION
KANSAS