

15-009-20865-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027Wichita, Kansas 67217  
NORTH


Locate well correctly on above  
Section Plat

## WELL PLUGGING RECORD

Barton County. Sec. 26 Twp. 16 Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines. 175' South of SE NW SW  
Lease Owner Vincent Oil Corporation  
Lease Name Lamatsch Well No. 1  
Office Address 901 Union Center Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Dec. 9 1974  
Application for plugging filed Dec. 9 1974  
Application for plugging approved Dec. 9 1974  
Plugging commenced Dec. 9 1974  
Plugging completed Dec. 9 1974  
Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation Depth to top Bottom Total Depth of Well 3380 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	298.50	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug 500 w/40 sx.  
2nd plug 210 w/25 sx.  
3rd plug 40 w/20 sx.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Woodman & Lannitti Drilling Co.  
Address 1008 Union National Bldg.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
K. T. Woodman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature)

K. T. Woodman

1008 Union National Bldg.

(Address)

Subscribed and Sworn to before me this 10th day of December, 1974

My commission expires Feb. 11, 1976

Justina Chamberlain

Notary Public.

K.T. WOODMAN  
RES. PHONE 733-0418  
OFF. PHONE 265-7650  
WICHITA, KANSAS

15-009-20865-00-00

D. J. IANNITTI  
PHONE 792-2921  
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY  
*Rotary Drilling Contractors*

1008 UNION NATIONAL BUILDING  
WICHITA, KANSAS 67202

December 10, 1974

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Company;	Vincent Oil Corporation
Farm;	#1 Lamatsch
Location;	175' South of SE NW SW
Section;	26-16-12W
County;	Barton
Comm;	December 1, 1974
Compl;	December 9, 1974
Contractor;	Woodman & Iannitti Drilling Co.
Total Depth;	3380'
Casing;	8 5/8" @ 298.50' w/150 sx.
Production;	D & A

Figures Indicate Bottom Of Formations:

40	Post Rock
180	Shale & Rock
245	Sand
270	Sand
302	Blue Shale
350	Shale
475	Sand
790	Red Bed
820	Anht
1045	Shale
1450	Shale
1555	Shale & Lime
1800	Shale & Lime
1970	Lime
2575	Shale & Lime
2786	Shale & Lime
2894	Lime
3112	Lime
3305	Lime
3355	Lime
3367	Arbuckle
3380	Total Depth

I certify the above to be a true and correct copy of the driller's log.

Woodman & Iannitti Drilling Co.

*K.T. Woodman*  
K. T. Woodman