

15-009-30084-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 26 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW SE NE

Lease Owner Schreiner Petroleum Company

Lease Name Dolecheck Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 8-20-65 19

Plugging completed 8-24-65 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truarj

Producing formation Depth to top Bottom Total Depth of Well 3346 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	324'	None
				5-1/2"	3340'	2670'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3346', sanded hole to 3320' and dumped 5 sacks of cement @ 3320' with dump bailer. Pulled 5 1/2" casing, bailed hole to 300', set rock bridge to 290' and dumped 25 sacks of cement @ 290'. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED 11-2-1965
NOV 2 1965

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1965

Milton J. Volin
Notary Public.

My commission expires May 20, 1968

GLICKMAN OIL COMPANY

P.O. Box 3104

Wichita, Kansas 67211

15-009-30084-00-00

DRILLERS WELL LOG

Company: Schreiner Petroleum Location: SW-SE-NE
 Farm: Dolecheck Well No. 1 26-16-12
 Barton County, Kansas
 Commenced: 5-24-65 Elevation:
 Completed: 6-2-65 Geologist: Bob Schreiner
 Total Depth: 3346'
 Casing: 8-5/8" set @ 337' cemented w/180 sxs Production:
 5-1/2" 15-1/2# 8-R Range 2 set @ 3331' w/100 sxs

Figures Indicate Bottom of Formations

45' Soil Rock & Clay
 780' Shale & Shells
 810' Anhydrite
 1015' Shale & Lime
 1465' Shale
 2070' Lime & Shale
 2195' Shale & Shells
 2845' Lime & Shale
 2925' Lime
 3250' Lime & Shale
 3334' Lime
 3346' Arbuckle Sand
 3346' Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 19 1965
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Dolecheck #1

Milton Glickman

 Milton Glickman

Subscribed and sworn to before me this 10th day of June, 1965

Lorella Schauf

 Lorella Schauf Notary Public

My Commission Expires: November 19, 1967