



**THE BRADLEY OIL COMPANY**

**Dolechak #1.**

**Location: 660' N. & 330' East of SE corner of Northwest Quarter of Section 26-16S-22W, Barton County, Kansas.**

**Contractors: The Triangle Drilling Co. Wichita, Kans.**

**Commenced Drilling: Aug 18, 1939.**

**Completed Drilling: Sept 7, 1939.**

**Elevation: 1918'**

**Set 10 1/2" surface casing 254' W/100' Deck**

0- 20	Surface clay
20- 375	shale & shell
375- 435	sand
435- 490	sand & lime shells
490- 550	semi- sand rock
550- 690	red bed
690- 795	shale & shells
795- 820	anhydrite
820-1235	shale & shells
1235-1445	silt & shells
1445-1490	shale & anhydrite
1490-1635	anhydrite
1635-1655	shale-shells
1655-1730	gray lime-sticky shale
1730-1760	shale lime sand str. sh.
1760-1780	shale & lime
1780-1840	lime-sand shale
1840-1870	sandy lime & shale
1870-1885	lime
1885-1910	sand sand rock
1910-1950	sandy lime
1950-1985	stick shale lime & sand
1985-2028	lime & shale
2028-2040	shale & lime, streaks of iron
2040-2110	lime, shale Pyrite of iron, shells
2110-2280	lime & shale
2280-2415	shale & lime
2415-2445	shale, lime sand
2445-2530	shale & lime shells
2530-2720	shale & lime
2720-2769	sticky shale
2769-2790	lime & shale
2790-2845	lime
2845-3100	lime & shale
3100-3102	shale
3102-3360	lime
3360-3375	lime & shale
3375-3385	coars, conglomerate, shale- sand
3385-3419	conglomerate
3419-3426	Dolomite T. D.

**Dry- plugged & abandoned.**

I hereby certify the above log to true and correct to the best of my knowledge and belief.

*James J. Miller*

**PLUGGING**  
 FILE SEC. 26-16-22W  
 BOOK PAGE 75 LINE 12

SEP 6 1939  
 STATE CORP. COMMISSION  
 CONSERVATION DIV.