

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued June 6, 1967.

Operator's Full Name Santa Fe Pipe & Supply, Inc.  
 Complete Address P. O. Box 562, Great Bend, Kansas 67530  
 Lease Name H. Hullman Well No. # 1  
 Location NE NE SW Sec. 7 Twp. 21 Rge. 14 (E) (W) W  
 County Stafford Total Depth 3724'  
 Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
 Other well as hereafter indicated         
 Plugging Contractor Santa Fe Pipe & Supply, Inc.  
 Address P. O. Box 562, Great Bend, Ks. 67530 License No. 574  
 Operation Completed: Hour 4:45 P.M. Day 21st Month June Year 1967

The above well was plugged as follows:

1001' of 8 5/8" surface pipe, cemented with 400 sacks. 3719' of 5 1/2" long  
string, cemented with 100 sacks. This is an open hole. Bottom of the hole  
was sanded to 3700', and cemented with 5 sacks, through the dump bailer.  
1999' of 5 1/2" long string was recovered from the hole. Fluid level in the  
was at 325', bridge plug and rock bridge from 325' to 315', and cemented  
with 25 sacks. Hole was filled with mud to 40', rock bridge from 40' to  
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/26/67INV. NO. 5447-W