

15.185.21453.0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 20- TWP. 21s RGE. 13 XE/W
 Location as in quarters or footage from lines:

200' E of G W/2 NW NE

Lease Owner Petroleum Energy, Inc.
 Lease Name FANSHIER Well No. 1
 Office Address 710 One Twenty Bldg., Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed Nov. 10 1981
 Application for plugging filed Nov. 10, 1981
 Plugging commenced Nov. 10, 1981
 Plugging completed Nov. 10, 1981
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation _____ Depth to top _____ bottom T.D. 3692

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug set @ 600' with 128 sacks 50/50 pozmix, 2% Gel, 3% cc thru drill pipe
Middle plug set @ 380' with 40 sacks " " " "
Top plug with solid bridge at 40' w/10 sacks cement
5 sacks cement in ~~xxxxxxx~~ mouse hole
10 sacks cement in rat hole and 3 sacks in water well

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Darrel Anderson (employee of owner) or ~~(owner or operator)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Darrel Anderson
 Box 823 Great Bend, Ks. 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 14 day of Nov, 19 81

Deborah M Hague
 Notary Public.

My Commission expires: 4-11-1982

RECEIVED
 STATE CORPORATION COMMISSION

NOV 23 1981
 11-23-1981
 CONSERVATION DIVISION
 Wichita Kansas

DRILLERS' WELL LOG

DATE COMMENCED: November 3, 1981
 DATE COMPLETED: November 10, 1981

Petroleum Energy, Inc.
 FANSHIER #1
 200' E of C W/2 NW NE
 Sec. 20-T21S-R13W
 Stafford County, Kansas

ELEVATION: 1899 GL
 1904 KB

0 - 735' Surface soil, sand, shale
 735 - 745' Anhydrite
 745 - 3215' Shale, Red Bed, Lime
 3215 - 3240' Shale & Lime
 3240 - 3252' Lime
 3252 - 3335' Shale
 3335 - 3349' Lime & Shale
 3349 - 3567' Lime
 3567 - 3689' Shale, Lime, Chert
 3689 - 3692' Dolomite
 3692' RTD

FORMATION DATA

ANHYDRITE	735
HEEBNER	3215
TORONTO	3240
DOUGLAS	3252
BROWN LIME	3335
LANSING KC	3349
BASE KC	3567
VIOLA	3598
ARBUCKLE	3689
RTD	3692

SURFACE PIPE: Set new
 8-5/8" 20# pipe at 245'
 with 275 sacks common cement,
 2% Gel, 3%cc.

AFFIDAVIT

STATE OF KANSAS
 COUNTY OF BARTON) SS

Darrel Anderson of lawful age does swear and state that the facts
 and statements herein contained are true and correct to the best of his knowledge.

Darrel Anderson

Subscribed and sworn to before me this 17 day of November 1981

Deiethy M. Waque
 Notary Public

My Comm. Expires: 4-11-1982

RECEIVED
 STATE CORPORATION COMMISSION

NOV 23 1981

CONSERVATION DIVISION
 Wichita, Kansas