

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

STAFFORD County, Sec. 20 Twp. 21s Rge. 13 (E)x (W)
Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner PETROLEUM, INC.,
Lease Name SCHARTZ 'P' Well No. 1
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JUNE 10 19 72
Application for plugging filed JUNE 12 19 72
Application for plugging approved JUNE 10 19 72
Plugging commenced JUNE 10 19 72
Plugging completed JUNE 10 19 72
Reason for abandonment of well or producing formation NO COMMERCIAL ZONE

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. R. BIBERSTEIN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3728' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	366	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


HEAVY MUD TO 600', FOLLOWED WITH 150 SACKS CEMENT. HEAVY MUD TO 350', FOLLOWED WITH 25 SACKS CEMENT. HEAVY MUD TO 40', FOLLOWED WITH 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.
(Signature) *Monte Chadd*

R.R. #2, GREAT BEND, KANSAS
(Address)
SUBSCRIBED AND FORGONE this 13 day of JUNE, 19 72



Richard H. Dumbler
Notary Public.
My commission expires MAY 28, 1973

WELL LOG

COMPANY Petroleum, Inc.

SEC. 20 T. 21S R. 13W

FARM Schartz 'P' NO. 1


LOC. SE NE SW

TOTAL DEPTH 3728'

COUNTY Stafford, Kansas

COMM. 6-2-72 COMP. 6-10-72

CONTRACTOR Garvey Drilling Company



CASING
8 5/8" @ 366' w/325sx

ELEVATION 1908' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 45' Clay & Sand
- 70' Shale & Sand
- 135' Hard Sand
- 366' Shale
- 790' Red Bed & Shale
- 830' Anhydrite
- 835' Shale
- 2155' Lime
- 2402' Lime & Shale
- 2925' Shale & Lime
- 3072' Lime & Shale
- 3330' Shale
- 3395' Lime & Shale
- 3444' Lime
- 3714' Chert
- 3718' Arbuckle
- 3728' Arbuckle
- 3728' RTD

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ES

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Schartz 'P' #1 well.

Subscribed and sworn to before me this 12th day of June 1972

My Commission Expires: July 8, 1974

Charlene Marker
Jerome A. [Signature]
NOTARY PUBLIC