

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biltmore Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above Section Plat

Stafford County, Sec. 20 Twp. 21 Rge. (E) 13 (W) 13  
 Location as "NE/CNW 1/4 SW 1/4" or footage from lines 330' N. & 990' W. of S/L Cor.  
 Lease Owner Cities Service Oil Company  
 Lease Name Schartz "B" Well No. 1  
 Office Address Bartlesville, Oklahoma  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed March 30, 19 52  
 Application for plugging filed March 30, 19 52  
 Application for plugging approved March 30, 19 52  
 Plugging commenced March 30, 19 52  
 Plugging completed March 30, 19 52  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production ---- 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
 Producing formation Depth to top Bottom Total Depth of Well 3770 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	361'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3770' - 350' heavy mud.  
 350' - 300' wood plug, 15 sacks cement  
 300' - 35' heavy mud  
 35' - base of cellar, wood plug and 10 sacks cement

4-15-52

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. C. Cooper  
 Address Box 751  
 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
 V. M. Conover (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *V. M. Conover*  
 Box 751, Great Bend, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 52

*W. B. Smith*  
 Notary Public.

My commission expires March 12, 1955.

PLUGGING  
 FILE SEC 20 21 R 13 W  
 BOOK PAGE 5 LINE 49

# WELL RECORD

15.185.11484.0000

Company Cities Service Oil Co. Well No. 1 Farm Schartz "B"  
 Location 330' North and 990' West of 3/4 Corner Sec. 20 T. 21 R. 13W  
 Elevation 1907 (1905 Gr.) County Stafford State Kansas  
 Drlg. Comm. March 14, 1952 Contractor Lohmann-Johnson Drilling Co., Inc.  
 Drlg. Comp. March 29, 1952 Acid None  
 T. D. 3770' Initial Prod. None - Dry Hole; NEA 3-20-52.

CASING RECORD:

8-5/8" @ 361' con. 250 ex cement

FORMATION RECORD:

sand	0-128
shale	362
red bed & shells	708
anhydrite	816
shale & shells	1323
salt	1345
shale & shells	1357
shale	1648
broken lime	1945
lime & shale	2275
shale & broken lime	2444
shale & lime	2792
lime	3237
shale	3340
lime	3640
lime & chert	3735
lime	3770 T. D.

Heetner	3238'
Brown Limestone	3363'
Lansing	3376'
Cherty Conglomerate	3629'
Viola	3636'
Simpson	3687'
Arbuckle	3730'
Penetration	40'
Total Depth	3770'

CYFO:	320'	0°
	600'	1°
	1300'	1°
	1800'	1°
	2300'	1°
	2800'	0°
	3300'	2°

Drill stem test 3403-38, open 1 hr., recovered 32' watery mud; B. H. P. 610# in 15 mins.

Drill stem test 3495-3512, open 1 hr., recovered 52' mud; B. H. P. 100# in 15 mins.

Drill stem test 3731-35, open 1 hr., recovered 18' mud; B. H. P. 800# in 15 mins.

Drill stem test 3734-37, open 1 hr., recovered 165' mud; B. H. P. 120# in 15 mins.

Drill stem test 3738-49, open 1 hr., recovered 28' mud; B. H. P. 510# in 15 mins.

**PLUGGING**

FILE SEC 20781 R 13W  
 BOOK PAGE 5 LINE 44