


WELL PLUGGING RECORD

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 20 Twp. 21 Rge. 13 (E) (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SW NE NW
Lease Owner Petroleum, Inc.
Lease Name Walters Well No. 1
Office Address 100 Derby Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 2, 1950
Application for plugging filed September 7, 1950
Application for plugging approved September 6, 1950
Plugging commenced September 2, 1950
Plugging completed September 2, 1950
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	207'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set at 207'. Cemented and displaced through drill pipe 15 sax. Filled hole with heavy mud to 30'. Placed wooden plug at 30'. Filled hole to surface with cement.

SEP 21 1950

9-8-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to 100 Derby Building, Petroleum, Inc.
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Eric H. Jager (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
100 Derby Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of September 19 50

Marjorie Bradshaw
Notary Public.

My commission expires October 27, 1952

PLUGGING
FILE SEC 20 T 21 R 13
BOOK PAGE 36 LINE 11

WELL LOG WALTER #1

Petroleum, Inc., Lease Owner

Section 20, Twp. 21S, Rge. 13W

Garvey Oil, Contractor

Location: SW NE NW

Rotary Total Depth: 3738'

County: Stafford, Kansas

Commenced: August 20, 1950

Elevation: 1906 D.F.

Completed: September 2, 1950

Casing: 207' of 8 5/8"

Figures below indicate bottom of formation:

70 Sand & Shale
 82 Sand
 120 Hard Sand
 202 Shale & Shells
 430 Sand & Pyrite
 690 Red Bed
 825 Anhydrite
 1125 Red Rock & Shale
 1320 Salt & Shale
 1610 Shale & Shells
 1720 Br. Lime
 1875 Lime
 2180 Lime & Shale
 2495 Shale & Shells
 2855 Lime & Shale
 3191 Lime
 3223 Lime & Shale
 3400 Lime
 3627 Lime & Shale
 3648 Shale
 3654 Viola Lime
 3675 Chert
 3678 Shale
 3738 Lime

Tops
 795 Anhydrite
 3240 Heebner
 3260 Toronto
 3277 Base Oread
 3364 Brown Lime
 3376 Lansing
 3580 Base K.C.
 3643 Viola
 3675 Simpson
 3728 Arbuckle

3738 R.T.D.

D & A

SEP 21 1950
PLUGGING
 FILE SEC 20 T 21 R 13W
 BOOK PAGE 26 LINE 11

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

STATE OF KANSAS
 SS.
 SEDGWICK COUNTY

Eric H. Jager
 Eric H. Jager

Subscribed to and sworn to before me, a Notary Public in said County and State this 5th day of September, 1950.

My commission expires: 10-27-52

Maryse Bradshaw
 Notary Public