



## CONTRACTOR'S WELL LOG

Operator Petroleum Inc. Farm Name Pursel No. 1  
 Location W<sup>1</sup> SW NE Sec. 20 TWP 21S Rge. 13W  
 Pool Name \_\_\_\_\_ County Stafford State Kansas  
 Commencement Date 12/16/49 Completion Date 1/9/50

## LOG OF WELL

\* All measurements from top of rotary bushing

From	DEPTH	To	FORMATION	DEVIATION From VERTICAL	REMARKS
0		55	Clay sand & gravel		
55		65	Lime with streaks iron		
65		117	Lime & P.T. Iron		
117		225	Shale-Shells		
225		296	Sand		
296		300	Shale-Shells		T.D. Surface
300		410	Grey bed		
410		710	Red bed	½° -500'	
710		760	Sand		
760		793	Red Bed		
793		820	Anhydrite lime		
820		1290	Shale-Shells	½° -919'	
1290		1450	Salt		
1450		1670	Shale-Shells	½° -1506'	
1670		1795	Lime		
1795		1870	Lime-Shale		
1870		1926	Lime		
1926		1990	Lime-Shale		
1990		2070	Lime		
2070		2865	Lime Shale	½° -2100'	
2865		3126	Lime		
3126		3152	Shale		
3152		3160	Lime		
3160		3330	Lime-Shale		
3330		3609	Lime		
3609		3641	Viola Chert		
3641		3650	Simpson		
3650		3712	Shale		
3712		3716	Arbuckle		
3716		3740	Lime A.R.B. Total Depth		

Set 300' (10 jts) 8 5/8" Casing

Plugged at 3740'

STATE OF KANSAS  
 SEDGWICK COUNTY

SS.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

*Eric H. Jager*  
 Eric H. Jager

Subscribed to and sworn to before me, a Notary Public in said County and State this 20th day of December, 1949.

*Margaret Bradshaw*  
 Notary Public

My commission expires: October 27, 1952.

