

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-22052-0000

API NUMBER 15-185-22,052

LEASE NAME Fanshier A

WELL NUMBER #1

SPOT LOCATION C E/2 NW NE

SEC. 20 TWP. 21 RGE. 13 (E) of (W)

COUNTY Stafford

Date Well Completed 8-24-84

Plugging Commenced 8-24-84

Plugging Completed 8-24-84

LEASE OPERATOR Petroleum Energy, Inc.

ADDRESS 415 First Nat'l Bank Bldg., Wichita, KS 67202

PHONE # (316) 265-2661 OPERATORS LICENSE NO. 5230

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top bottom T.D. 3689'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size 8 5/8	Put in 343'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Spotted 50 sx cement @ 810' thru drill pipe.

Spotted 40 sx cement @ 390' thru drill pipe.

Spotted 10 sx cement @ 40' thru drill pipe.

Spotted 5 sx cement in water well.

Spotted 10 sx cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as prepared that the same are true and correct, so help me God.


RECEIVED
STATE CORPORATION COMMISSION

SEP 07 1984


(Signature) Ernest Sifford
(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

before me this 6th day of September, 1984

David F. James
Notary Public



My Commission expires:



15.185.22052.0000

WHITE

ANDELLISDRILLING, Inc.

DRILLERS LOG

OPERATOR: Petroleum Energy, Inc.
 415 First Nat'l Bank Bldg.
 Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
 Wichita, Ks. 67202

Lease Name Fanshier A Well No. #1

Sec. 20 T. 21S R. 13W Spot C E/2 NW NE

County Stafford State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 343' with 300 sx. 3% cc

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3689'

Drilling Commenced 8-18-84 Drilling Completed 8-24-84

Formation	From	To	Tops
Cellar	0	7	Anhydrite - 790
Sand	7	100	
Shale, Lime	100	587	
Shale	587	790	
Shale, Lime	790	2235	
Lime, Shale	2235	3515	
Lime	3515	3689	

RECEIVED
 STATE CORPORATION COMMISSION

SEP 07 1984

CONSERVATION DIVISION
 Wichita, Kansas