

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas


RECEIVED
DEC 27 1969

WELL PLUGGING RECORD

Stafford County. Sec 2 Twp. 21 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SE SE
Lease Owner Morris Sitrin, Inc.
Lease Name V. Address #1 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/10/69 19
Plugging completed 12/12/69 19
Reason for abandonment of well or producing formation depleted.

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justice
Producing formation Depth to top Bottom Total Depth of Well 3535 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	246'	none
				5 1/2"	3532'	2109'

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3535' and ran sand to 3250', dumped 5 sacks of cement. Shot pipe at 2900, 2644, 2458, worked pipe loose and pulled 66 joints. Halliburton squeezed well with 30 sacks mud and 100 sacks cement.

PLUGGING COMPLETE.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1969



My commission expires 2/25/71
Margaret Melcher Notary Public.

RECEIVED
DEC 23 1969

15.185.36168-0000

DRILL LOG

VIRGINIA AN SS NO. 1

CASING RECORD: **COMPANY:** Circ Oil Co. **DESCRIPTION:**
 246' of 8-5/8" **CONTRACTOR:** Sage Drilling Co. NW SE SE
 w/250 sax cement **COMMENCED:** September 23, 1965 Sec. 2-21S-13W
TOTAL DEPTH: **COMPLETED:** September 29, 1965 Stafford Co., Kansas
 3535'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Sand	0	247	
Shale	247	265	
Red Bed & Sand	265	694	
Anhydrite	694	721	
Shale	721	1500	
Sandy Lime	1500	1800	
Lime	1800	2105	
Shale & Sandy Lime	2105	2455	
Shale & Lime	2455	2815	
Lime w/Shale	2815	3067	
Lime	3067	3107	
Shale	3107	3232	
Lime & Shale	3232	3325	
Lime	3325	3535	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 25 1969
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

Lawrence F. Gray

 Lawrence F. Gray

Subscribed and sworn to before me this 22nd day of October, 1965.

Louise K. Whitted

 Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.