

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,063,0000

LEASE NAME Address "A"

WELL NUMBER 1

990 Ft. from W/N Line of Section (circle one)

660 Ft. from W/W Line of Section (circle one)

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.



SPOT LOCATION S/2 NW NW

SEC. 2 TWP. 21S s. RGE 13 (N) or (W)

COUNTY Stafford

Date Well Completed 8/29/84

Date Plugging Commenced 4/12/00

Date Plugging Completed 4/14/00

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468

CITY, STATE, ZIP Tulsa, OK 74121-1468

PHONE# (918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation(s) LKC Depth to Top 3276 Bottom 3570 T.D. 3651

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	CONVERSION TO FORMATION DIVISION Wichita, Kansas	PUT IN	PULL OUT
LKC	Oil	3276	8 5/8	378	-0-
			1 1/2	3650	2085

RECEIVED
STATE CORPORATION COMMISSION
MAY 30 2000
CONSERVATION DIVISION
Wichita, Kansas

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3200' & dumped 5 sxs cmt on top. Shot pipe @ 2085'. Pumped 400# hulls, 10 sxs gel & 50 sxs cmt. Released plug. Pumped add'l 125 sxs 60/40 poz w/6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mike's Testing & Salvage, Inc.

License No. 31529

Address P. O. Box 467, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468



26th day of May, 192000

Marilyn J. Clifton
Notary Public

R