


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 2 Twp. 21S Rge. (E) 13W(W)

Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner Circle Oil Company, Inc.
Lease Name Charles ANDRESS Well No. 2
Office Address 500 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 22, 19 66
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced May 22, 19 66
Plugging completed May 22, 19 66
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3615 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	256'	8-5/8"	5/14/66	----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 240 Feet;
HOWCO Plug and Hull Plug and 25 sacks
Cement thru the Drill Pipe; Heavy Mud
to 40 feet; 1/2 sack Hulls, Plug bridged
with Kelley and 10 sacks Cement to Base
of Cellar; 2 sacks in Rat Hole.
Job completed at 6:45 P.M.

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 66
Louise K. Whitted
Louise K. Whitted, Notary Public.

My commission expires November 26, 1966

DRILLERS LOGCHARLES ANDRESS NO. 2

CASING RECORD:	COMPANY:	Circle Oil Co.	DESCRIPTION:
8-5/8" @ 256' w/200 sax cement	CONTRACTOR:	Sage Drilling Co.	SE NE SW Sec. 2=21S-13W, Stafford Co., Kansas
TOTAL DEPTH: 3615'	COMMENCED:	May 14, 1966	ELEVATION: 1871KB
	COMPLETED:	May 22, 1966	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	160	
Shale & Shells	160	256	
Shale & Red Bed & Sand	256	1595	
Sandy Lime & Shale	1595	1830	
Shale & Lime	1830	3078	
Lime & Shale	3078	3522	
Lime	3522	3525	
Lime & Shale	3525	3615	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 24th day of May, 1966.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1966

CONSERVATION DIVISION
Wichita, Kansas